Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Cross Road 38 (W1827)		1	210.00	5.00	0.04	42.00		
	Cross Road 40 (W1190)		1	32.00	4.30	0.04	5.50		
	Cross Road 43 (W1815)		1	31.00	4.20	0.04	5.21		
	Wajid Layout								
	Cross Road(W0278)		1	278.00	6.00	0.04	66.72		
	Thanisandra Mn Rd LHS								
	Rajmid Masjid Road(W0992)		1	441.00	5.30	0.04	93.49		
	Abubakar Masjid Road(W0976)		1	440.00	5.70	0.04	100.32		
	Saraipalya								
	Cross Road A		1	140.00	4.60	0.04	25.76		
	Cross Road B		1	152.00	4.60	0.04	27.97		
	Cross Road C		1	159.00	4.60	0.04	29.26		
	Railway Mens Layout								
	1st main Rd		1	189.00	6.00	0.04	45.36		
	2nd main Rd(W0190)		1	270.00	5.60	0.04	60.48		
	3rd main Rd(W0194)		1	157.00	6.00	0.04	37.68		
	4th main Rd(W0200)		1	74.00	6.00	0.04	17.76		
	5th main Rd(W0254)		1	284.00	5.40	0.04	61.34		
	Saraipalya								
	Thanisandra Mn Rd RHS								
	Cross Rd 27(W1795)		1	90.00	4.10	0.04	14.76		
	Cross Rd 28		1	181.00	6.00	0.04	43.44		
	Cross Rd 31(W1763)		1	177.00	5.50	0.04	38.94		
	Cross Rd 32(W1767)		1	119.00	5.00	0.04	23.80		
	Cross Rd 34(W1773)		1	196.00	4.80	0.04	37.63		
	Vidyasagar Road(W1108)		1	125.00	5.60	0.04	28.00		
	Over Lay Roads								
	Rachenahalli								
	Main Road(W0365)		1	628.00	6.90	0.04	173.33		
	Cross Rd 14(W1147)		1	45.00	5.00	0.04	9.00		
	Saraipalya								
	Thanisandra Mn Rd RHS								
	Cross Road 1(W1565)		1	274.00	5.30	0.04	58.09		
	Cross Road 5(W0992)		1	587.00	6.00	0.04	140.88		
							4150.58	**7753.90**	**32183151.25**
18	KSRRB M800-13.**Road Marking** with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface/ Concrete Surface: Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 standards specified. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803(P.No-182,I No-24.15)								
	Basic rate	429.00							
	Area Weightage 6%	25.74							
	Total	**454.74**							
		Sqm							
	Dasarahalli								

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	10th cross (W0911)		2.5	164.00	0.10		41.00		
	11th cross (W0917)		2.5	176.00	0.10		44.00		
	12th cross (W0921)		2.5	186.00	0.10		46.50		
	13th cross (W0927)		2.5	195.00	0.10		48.75		
	1st cross (W0923)		0.5	33.00	0.10		1.65		
	2nd cross (W0919)		0.5	56.00	0.10		2.80		
	3rd cross (W0483)		0.5	69.00	0.10		3.45		
	10th cross (W0485)		2.5	195.00	0.10		48.75		
	Sub cross road (W0913)		0.5	126.00	0.10		6.30		
	Dasarahalli Extension								
	Cross Rd 1 (W0300)		0.5	143.00	0.10		7.15		
	Cross Rd 2 (W0387)		0.5	138.00	0.10		6.90		
	Cross Rd 3 (W0585)		0.5	44.00	0.10		2.20		
	Cross Rd 4 (W0300)		0.5	67.00	0.10		3.35		
	Cross Rd 5 (W0316)		2.5	183.00	0.10		45.75		
	Dasarahalli								
	Cross Rd 1 (W0338)		0.5	47.00	0.10		2.35		
	Cross Rd 2 (W0328)		0.5	45.00	0.10		2.25		
	Cross Rd 3 (W0322)		0.5	45.00	0.10		2.25		
	Cross Rd 4 (W0320)		0.5	46.00	0.10		2.30		
	Cross Rd 5 (W0310)		0.5	46.00	0.10		2.30		
	Cross Rd 6 (W0306)		0.5	47.00	0.10		2.35		
	Cross Rd 7 (W0280)		0.5	69.00	0.10		3.45		
	Cross Rd 8 (W302)		0.5	125.00	0.10		6.25		
	Cross Rd 9 (W0499)		0.5	56.00	0.10		2.80		
	Cross Rd 10 (W0590)		0.5	30.00	0.10		1.50		
	Cross Rd 11 (W0905)		0.5	69.00	0.10		3.45		
	Dasarahalli								
	4th cross (W0461)		2.5	148.00	0.10		37.00		
	5th cross (W0465)		2.5	334.00	0.10		83.50		
	6th cross (W0471)		2.5	387.00	0.10		96.75		
	7th cross (W0475)		2.5	379.00	0.10		94.75		
	9th cross (W0479)		2.5	338.00	0.10		84.50		
	Sub cross road		0.5	37.00	0.10		1.85		
	10th cross (W0909)		0.5	63.00	0.10		3.15		
	11th cross (W0915)		0.5	59.00	0.10		2.95		
	12th cross (W0919)		0.5	49.00	0.10		2.45		
	13th cross (W0925)		0.5	40.00	0.10		2.00		
	Cross Rd 12 (W0939)		2.5	256.00	0.10		64.00		
	Cross Rd 13 (W0586)		0.5	28.00	0.10		1.40		
	Cross Rd 14 (W0588)		0.5	32.00	0.10		1.60		
	Cross Rd 15 (W0594)		0.5	32.00	0.10		1.60		
	Cross Rd 16 (W093)		0.5	65.00	0.10		3.25		
	Cross Rd 17 (W901)		0.5	57.00	0.10		2.85		
	Maruti Layout								
	12th cross (W0495)		2.5	510.00	0.10		127.50		
	13th cross (W0491)		2.5	268.00	0.10		67.00		
	Maruti Layout								
	1st main Rd, LHS								
	1st A cross (W0577)		0.5	40.00	0.10		2.00		

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	2nd A cross (W0573)		0.5	71.00	0.10		3.55		
	3rd A cross (W0569)		0.5	93.00	0.10		4.65		
	Cross Rd (W0557)		0.5	90.00	0.10		4.50		
	Maruti Layout								
	14th cross (W0447)		2.5	142.00	0.10		35.50		
	5th cross (W0553)		2.5	173.00	0.10		43.25		
	Sub cross road (W0356)		0.5	24.00	0.10		1.20		
	6th A cross (W0543)		2.5	293.00	0.10		73.25		
	4th cross (W0971)		2.5	127.00	0.10		31.75		
	Sub cross road (W0600)		0.5	44.00	0.10		2.20		
	3rd cross (W0563)		2.5	245.00	0.10		61.25		
	1st main Rd, RHS								
	1st cross (W0571)		0.5	55.00	0.10		2.75		
	2nd cross (W0567)		0.5	66.00	0.10		3.30		
	3rd cross (W0561)		0.5	82.00	0.10		4.10		
	4th cross (W0555)		0.5	58.00	0.10		2.90		
	5th cross (W0545)		2.5	124.00	0.10		31.00		
	A Cross (W0598)		2.5	132.00	0.10		33.00		
	18th A cross (W0945)		0.5	66.00	0.10		3.30		
	18th B cross (W0941)		2.5	212.00	0.10		53.00		
	18th cross (W0505)		2.5	118.00	0.10		29.50		
	Sub cross road (W0531)		2.5	215.00	0.10		53.75		
	Rachenahalli								
	Cross Rd 1		0.5	127.00	0.10		6.35		
	1st cross (W0699)		0.5	139.00	0.10		6.95		
	2nd cross (W0691)		0.5	103.00	0.10		5.15		
	3rd cross (W0683)		0.5	100.00	0.10		5.00		
	1st cross (W0685)		0.5	112.00	0.10		5.60		
	2nd cross continued (W0317)		2.5	167.00	0.10		41.75		
	Cross Rd 2 (W0715)		0.5	85.00	0.10		4.25		
	Cross Rd 3 (W0656)		0.5	120.00	0.10		6.00		
	Cross Rd 4 (W0452)		0.5	130.00	0.10		6.50		
	Cross Rd 5 (W0448)		0.5	130.00	0.10		6.50		
	Cross Rd 6 (W0444)		0.5	135.00	0.10		6.75		
	Cross Rd 7(W0222)		0.5	128.00	0.10		6.40		
	Cross Rd 8 (W0218)		0.5	129.00	0.10		6.45		
	Cross Rd 9 (W0210)		0.5	130.00	0.10		6.50		
	Cross Rd 10		0.5	99.00	0.10		4.95		
	Cross Road A		0.5	140.00	0.10		7.00		
	Cross Road B		0.5	144.00	0.10		7.20		
	Cross Road C		2.5	153.00	0.10		38.25		
	Cross Road D		2.5	150.00	0.10		37.50		
	Rachenahalli								
	Sub road (W0460)		2.5	236.00	0.10		59.00		
	2nd cross (W0669)		0.5	120.00	0.10		6.00		
	Anjanadri Layout								
	Cross Rd 2		0.5	24.00	0.10		1.20		
	Cross Rd 3		0.5	49.00	0.10		2.45		
	Saraipalya								

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Thanisandra Mn Rd RHS								
	Cross Road 2 (W1082)		2.5	172.00	0.10		43.00		
	Cross Road 6 (W1038)		2.5	221.00	0.10		55.25		
	Cross Road 7 (W1042)		0.5	81.00	0.10		4.05		
	Cross Road 8 (W1561)		0.5	34.00	0.10		1.70		
	Cross Road 9		0.5	21.00	0.10		1.05		
	Cross Road 10 (W1557)		0.5	34.00	0.10		1.70		
	Cross Road 11 (W1547)		0.5	84.00	0.10		4.20		
	Cross Road 12 (W1547)		0.5	21.00	0.10		1.05		
	Cross Road 13 (W1537)		0.5	34.00	0.10		1.70		
	Cross Road 14 (W1537)		0.5	24.00	0.10		1.20		
	Cross Road 15 (W1533)		0.5	33.00	0.10		1.65		
	Cross Road 16 (W1533)		0.5	44.00	0.10		2.20		
	Cross Road 17 (W1527)		0.5	30.00	0.10		1.50		
	Cross Road 18 (W1527)		0.5	44.00	0.10		2.20		
	Cross Road 19 (W1523)		0.5	28.00	0.10		1.40		
	Cross Road 20 (W1523)		0.5	46.00	0.10		2.30		
	Cross Road 21 (W1517)		2.5	150.00	0.10		37.50		
	Cross Road 22 (W1058)		0.5	81.00	0.10		4.05		
	Cross Road 23 (W1052)		0.5	84.00	0.10		4.20		
	Cross Road 24 (W1046)		0.5	86.00	0.10		4.30		
	Cross Road 26 (W1805)		0.5	92.00	0.10		4.60		
	Cross Road 33 (W1056)		0.5	74.00	0.10		3.70		
	Cross Road 36 (W1176)		2.5	232.00	0.10		58.00		
	Cross Road 38 (W1827)		2.5	210.00	0.10		52.50		
	Cross Road 40 (W1190)		0.5	32.00	0.10		1.60		
	Cross Road 43 (W1815)		0.5	31.00	0.10		1.55		
	Anjanadri Layout								
	Cross Rd 8 (W1189)		0.5	125.00	0.10		6.25		
	Cross Rd 9 (W1179)		0.5	116.00	0.10		5.80		
	Cross Rd 10(W1169)		0.5	116.00	0.10		5.80		
	Cross Rd 11(W1159)		0.5	117.00	0.10		5.85		
	Cross Rd 12(W1151)		0.5	45.00	0.10		2.25		
	Cross Rd 13(W1155)		0.5	73.00	0.10		3.65		
	Cross Rd 14(W1147)		0.5	92.00	0.10		4.60		
	5th cross		0.5	72.00	0.10		3.60		
	Sub cross road		0.5	30.00	0.10		1.50		
	Sub cross road		0.5	30.00	0.10		1.50		
	6th cross		0.5	59.00	0.10		2.95		
	Wajid Layout								
	Cross Road(W0278)		2.5	278.00	0.10		69.50		
	Thanisandra Mn Rd LHS								
	Rajmid Masjid Road(W0992)		2.5	441.00	0.10		110.25		
	Abubakar Masjid Road(W0976)		2.5	440.00	0.10		110.00		
	Saraipalya								
	Cross Road A		0.5	140.00	0.10		7.00		
	Cross Road B		0.5	152.00	0.10		7.60		
	Cross Road C		0.5	159.00	0.10		7.95		

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Railway Mens Layout								
	1st main Rd		2.5	189.00	0.10		47.25		
	2nd main Rd(W0190)		2.5	270.00	0.10		67.50		
	3rd main Rd(W0194)		2.5	157.00	0.10		39.25		
	4th main Rd(W0200)		0.5	74.00	0.10		3.70		
	5th main Rd(W0254)		2.5	284.00	0.10		71.00		
	Saraipalya								
	Thanisandra Mn Rd RHS								
	Cross Rd 27(W1795)		0.5	90.00	0.10		4.50		
	Cross Rd 28		2.5	181.00	0.10		45.25		
	Cross Rd 31(W1763)		2.5	177.00	0.10		44.25		
	Cross Rd 32(W1767)		2.5	119.00	0.10		29.75		
	Cross Rd 34(W1773)		2.5	196.00	0.10		49.00		
	Vidyasagar Road(W1108)		2.5	125.00	0.10		31.25		
	Over Lay Roads								
	Rachenahalli								
	Main Road(W0365)		2.5	628.00	0.10		157.00		
	Cross Rd 14(W1147)		0.5	45.00	0.10		2.25		
	Cross Rd 15		0.5	34.00	0.10		1.70		
	Cross Rd 16		0.5	28.00	0.10		1.40		
	Anjanadri Layout								
	2nd cross		2.5	510.00	0.10		127.50		
	Saraipalya								
	Thanisandra Mn Rd RHS								
	Cross Road 1(W1565)		2.5	274.00	0.10		68.50		
	Cross Road 5(W0992)		2.5	587.00	0.10		146.75		
							3373.30	**454.74**	**1533974.44**
19	KSRRB M200-24. **Dismantling of cement concrete pavement** by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials upto a lead of 1000 metrers, stacking serviceable and unserviceable materials seperately complete as per specifications. MORTH Specification No. 202.(I No-18.47,P No-140)								
	Basic rate	899.00							
	Area Weightage 6%	53.94							
	Sub Total =	952.94							
	10Km Lead =(2*1.28*10)	25.60							
	Total Rate Rs. =	**978.54**							
		Cum							
	CC Roads								
	Anjanadri Layout								
	3rd cross		1	92.00	5.80	0.25	133.40		
	Cross Road 11		1	37.00	4.00	0.25	37.00		
	Cross Road 12		1	47.00	3.50	0.25	41.13		
	Cross Road 13		1	47.00	3.50	0.25	41.13		
	Saraipalya								
	Thanisandra Mn Rd LHS								
	A cross								
	Sub road 1 (W1000)		1	66.00	3.70	0.25	61.05		
	Sub road 2 (W1000)		1	53.00	3.30	0.25	43.73		

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Sub road 3 (W1479)		1	43.00	3.30	0.25	35.48		
	B cross								
	Sub road 1 (W1471)		1	63.00	3.50	0.25	55.13		
	Sub road 2 (W1471)		1	49.00	3.50	0.25	42.88		
	Sub road 3 (W1469)		1	75.00	3.80	0.25	71.25		
	C cross								
	Sub road 1 (W1463)		1	58.00	3.70	0.25	53.65		
	Sub road 2 (W1463)		1	46.00	3.90	0.25	44.85		
	Sub road 3 (W1461)		1	76.00	4.00	0.25	76.00		
	D cross								
	Sub road 1 (W1455)		1	54.00	3.50	0.25	47.25		
	Sub road 2 (W1455)		1	44.00	3.50	0.25	38.50		
	Sub road 3 (W1451)		1	54.00	3.80	0.25	51.30		
	Cross Road 1 (W0998)		1	50.00	4.00	0.25	50.00		
	Cross Road 2 (W1449)		1	32.00	3.50	0.25	28.00		
	Cross Road 3 (W1445)		1	36.00	3.50	0.25	31.50		
	Thanisandra Mn Rd RHS								
	Sub road 1 (W1793)		1	38.00	4.30	0.25	40.85		
	Sub road 2 (W1791)		1	38.00	2.50	0.25	23.75		
	Sub road 3 (W1789)		1	34.00	3.40	0.25	28.90		
							1076.70	**978.54**	**1053594.02**
20	KSRRB M600-1.Providing and Constructing **dry lean cement concrete mix CC 1:5:10** base with OPC 25mm and down size graded granite metal coarse aggregate at 0.86cum and fine aggregates @0.58cum over a prepared sub-base, coarse and fine aggregate conforming to IS: 383-2016,aggregate cement ratio not to exceed 15:1, Aggregate gradation after blending to be as per Table 600-1,optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver, compacting with 8-10 tonnes vibratory roller, finishing and curing complete as per specifications. Clause 601of MORTH V Revision and IS 456 Table-5, with OPC at 150 kg/cum and coarse aggregate 0.86cum, fine aggregate 0.58cum using Concrete Batch mix Plant at 75 cum/hr capacity with Slip form paver with electronic sensor. (P.No-174,I No-22.1.1)								
	Basic rate	3585.00							
	Area Weightage 6%	215.10							
	Total	**3800.10**							
		Cum							
	CC Roads								
	Anjanadri Layout								
	3rd cross		1	92.00	5.80	0.15	80.04		
	Cross Road 11		1	37.00	4.00	0.15	22.20		
	Cross Road 12		1	47.00	3.50	0.15	24.68		
	Cross Road 13		1	47.00	3.50	0.15	24.68		
	Saraipalya								
	Thanisandra Mn Rd LHS								
	A cross								
	Sub road 1 (W1000)		1	66.00	3.70	0.15	36.63		
	Sub road 2 (W1000)		1	53.00	3.30	0.15	26.24		
	Sub road 3 (W1479)		1	43.00	3.30	0.15	21.29		
	B cross								
	Sub road 1 (W1471)		1	63.00	3.50	0.15	33.08		

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Sub road 2 (W1471)		1	49.00	3.50	0.15	25.73		
	Sub road 3 (W1469)		1	75.00	3.80	0.15	42.75		
	C cross								
	Sub road 1 (W1463)		1	58.00	3.70	0.15	32.19		
	Sub road 2 (W1463)		1	46.00	3.90	0.15	26.91		
	Sub road 3 (W1461)		1	76.00	4.00	0.15	45.60		
	D cross								
	Sub road 1 (W1455)		1	54.00	3.50	0.15	28.35		
	Sub road 2 (W1455)		1	44.00	3.50	0.15	23.10		
	Sub road 3 (W1451)		1	54.00	3.80	0.15	30.78		
	Cross Road 1 (W0998)		1	50.00	4.00	0.15	30.00		
	Cross Road 2 (W1449)		1	32.00	3.50	0.15	16.80		
	Cross Road 3 (W1445)		1	36.00	3.50	0.15	18.90		
	Thanisandra Mn Rd RHS								
	Sub road 1 (W1793)		1	38.00	4.30	0.15	24.51		
	Sub road 2 (W1791)		1	38.00	2.50	0.15	14.25		
	Sub road 3 (W1789)		1	34.00	3.40	0.15	17.34		
							646.02	**3800.10**	**2454940.60**
21	Constructing un-reinforced, **plain cement concrete for pavements using Grade concrete M30** with OPC at 360 kg/cum and coarse aggregate 0.69cum, fine aggregate 0.46cum. over a prepared base with OPC coarse aggregate at 0.69 cum, fine aggregates at 0.46 cum,Coarse and fine aggregate conforming to IS:383-2016, with Superplastizer at 3 lts conforming to IS 9103-2008. mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). & Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints,including groove cutting charges, joint filler, separation membrane of impermiable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades, textured with texturing machine, and curing including cost of all materials, labour,hire charges of machineries,all lead & lift charges etc., complete as per specifications. (P.No-176,I No-22.6.1)								
	Basic rate	4916.00							
	Area Weightage 6%	294.96							
	Total	**5210.96**							
		Cum							
	CC Roads								
	Anjanadri Layout								
	3rd cross		1	92.00	5.80	0.15	80.04		
	Cross Road 11		1	37.00	4.00	0.15	22.20		
	Cross Road 12		1	47.00	3.50	0.15	24.68		
	Cross Road 13		1	47.00	3.50	0.15	24.68		
	Saraipalya								
	Thanisandra Mn Rd LHS								
	A cross								
	Sub road 1 (W1000)		1	66.00	3.70	0.15	36.63		
	Sub road 2 (W1000)		1	53.00	3.30	0.15	26.24		
	Sub road 3 (W1479)		1	43.00	3.30	0.15	21.29		
	B cross								

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Sub road 1 (W1471)		1	63.00	3.50	0.15	33.08		
	Sub road 2 (W1471)		1	49.00	3.50	0.15	25.73		
	Sub road 3 (W1469)		1	75.00	3.80	0.15	42.75		
	C cross								
	Sub road 1 (W1463)		1	58.00	3.70	0.15	32.19		
	Sub road 2 (W1463)		1	46.00	3.90	0.15	26.91		
	Sub road 3 (W1461)		1	76.00	4.00	0.15	45.60		
	D cross								
	Sub road 1 (W1455)		1	54.00	3.50	0.15	28.35		
	Sub road 2 (W1455)		1	44.00	3.50	0.15	23.10		
	Sub road 3 (W1451)		1	54.00	3.80	0.15	30.78		
	Cross Road 1 (W0998)		1	50.00	4.00	0.15	30.00		
	Cross Road 2 (W1449)		1	32.00	3.50	0.15	16.80		
	Cross Road 3 (W1445)		1	36.00	3.50	0.15	18.90		
	Thanisandra Mn Rd RHS								
	Sub road 1 (W1793)		1	38.00	4.30	0.15	24.51		
	Sub road 2 (W1791)		1	38.00	2.50	0.15	14.25		
	Sub road 3 (W1789)		1	34.00	3.40	0.15	17.34		
							646.02	**5210.96**	**3366384.38**
								Total Construction Cost	**125648801.97**
								Towards GST 12%	**15077856.24**
								Tender Premium 5%	**6282440.10**
								DPR & PMC Charges 2%	**2990000.00**
								Misccellaneous & Rounding Off	**901.69**
								Sub Total	**150000000.00**

Certificate

1. The workspot was inspected and works is found to be necessary.
2. The area comes within the Bruhat Bangalore Mahanagara Palike limits.
3. The rates adopted based on the PWD SR,Bangalore circle for year 2018-2019, issue rates dated 03-01-2020 and Data Rates

4) APPROVED DATA RATE COPY TO BE ENCLOSED

Assistant Engineer
Project Division Yelahanka
BBMP Bangalore

Asst. Executive Engineer
Project Division Yelahanka
BBMP Bangalore

Asst. Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore - 92

Executive Engineer
Project Division Yelahanka
BBMP Bangalore

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Technical Sanction
Accorded For RS 1500 Cr
Head of A/C P 3761
CER NO :..35..... Dt:17.06.2020

CE (YNK)

Administrative Approval
Accorded For RS. 1500 crores lakhs
Head of A/C..... P 3761
CER NO :.....51..... Dt:..09/11/2020

E.E. (Project)